

**Laboratory Evaluation to Assess a Proposed
Test Method to Determine Transient Combustion Spillage**

A Confidential Report to:

Natural Resources Canada
580 Booth Street
13th Floor, Rm. 13D
Ottawa, Ontario
K1A 0E4

Attention:

Mr. James Glouchkow

Telephone:

613-943-9235

Fax:

613-996-9909

Report No.:

04-06-M278b Rev. 1
33 Pages, 2 Appendices

Date:

August 29, 2005

TABLE OF CONTENTS

List of Tables3
List of Figures4
List of Test Data Sheets (Appendix B)4
1.0 Introduction5
2.0 Test Methodology6
 2.1 Depressurization Spillage - General Test Procedure6
 2.2 Transient Spillage Test Procedure6
 2.2.1 Transient Spillage Calculations7
 2.2.2 Steady State Depressurization Spillage Test Procedure7
 2.2.3 Steady State Depressurization Spillage Calculations8
 2.3 Static Leakage Test Procedure8
 2.3.1 Static Leakage Calculations8
3.0 Transient Depressurization Spillage Test Set-Up9
 3.1 Sample Number 04-06-M0278-1 - Power Vented Water Heater9
 3.2 Sample Number 04-06-M0278-2 - Mid-Efficiency Furnace10
 3.3 Sample Number 04-06-M0278-4 - Power Vented Water Heater11
 3.4 Sample Number 04-06-M0278-5 - High Efficiency Furnace12
 3.5 Sample Number 04-06-M0278-6 - High Efficiency Furnace13
 3.6 Sample Number 04-06-M0278-7 - Direct Vent Fireplace Insert14
 3.7 Sample Number 04-06-M0278-8 - Direct Vent Zero Clearance Fireplace15
4.0 Leakage Testing17
 4.1 Sample Numbers 04-06-M0278-1 and 04-06-M0278-4 - Power Vented Water Heater17
 4.2 Sample Number 04-06-M0278-2 - Mid-Efficiency Furnace17
 4.3 Sample Numbers 04-06-M0278-5 and 04-06-M0278-6 - High Efficiency Furnaces18
 4.4 Sample Numbers 04-06-M0278-7 and 04-06-M0278-8 - Direct Vent Fireplaces19
5.0 Test Results20
 5.1 Transient Spillage Test Results20
 5.1.1 Sample Number 04-06-M0278-1 - Power Vented Water Heater20
 5.1.2 Sample Number 04-06-M0278-2 - Mid-Efficiency Furnace - Test #121
 5.1.2.1 Sample Number 04-06-M0278-2 - Mid-Efficiency Furnace - Test #221
 5.1.3 Sample Number 04-06-M0278-4 - Power Vented Water Heater - Test #122
 5.1.3.1 Sample Number 04-06-M0278-4 - Power Vented Water Heater - Test #222
 5.1.4 Sample Number 04-06-M0278-5 - High Efficiency Furnace23
 5.1.5 Sample Number 04-06-M0278-6 - High Efficiency Furnace23
 5.1.6 Sample Number 04-06-M0278-7 - Direct Vent Fireplace Insert - Test #124
 5.1.6.1 Sample Number 04-06-M0278-7 - Direct Vent Fireplace Insert - Test #224
 5.1.6.2 Sample Number 04-06-M0278-7 - Direct Vent Fireplace Insert - Test #325
 5.1.6.3 Sample Number 04-06-M0278-7 - Direct Vent Fireplace Insert - Test #425
 5.1.7 Sample Number 04-06-M0278-8 - Direct Vent Zero Clearance Fireplace26
 5.2 Steady State Depressurization Spillage Test Results27

TABLE OF CONTENTS (cont'd)

5.2.1 Sample Number 04-06-M0278-1 - Power Vented Water Heater27
5.2.2 Sample Number 04-06-M0278-2 - Mid-Efficiency Furnace28
5.3 Static Leakage Test Results.....29
5.3.1 Sample Numbers 04-06-M0278-1 and 04-06-M0278-4 - Power Vented Water Heaters.....29
5.3.2 Sample Number 04-06-M0278-2 - Mid-Efficiency Furnace29
5.3.3 Sample Number 04-06-M0278-5 - High Efficiency Furnace29
5.3.4 Sample Number 04-06-M0278-6 - High Efficiency Furnace30
5.3.5 Sample Number 04-06-M0278-7 - Direct Vent Fireplace Insert.....30
5.3.6 Sample Number 04-06-M0278-8 - Direct Vent Zero Clearance Fireplace30
6.0 Testing Comments32

LIST OF TABLES

Table 1 – Appliance Descriptions and Assigned BMTC Sample Numbers5
Table 2 – Steady State Depressurization Spillage Test Data - Sample No. 04-06-M0278-127
Table 3 – Steady State Depressurization Spillage Test Data - Sample No. 04-06-M0278-228
Table 4 – Summary of Test Results31
Table 5 – Details of Equipment and Instrumentation Used Appendix A

LIST OF FIGURES

Figure 1 – Water Heater Vent Configuration (Sample No. 04-06-M0278-1)9
Figure 2 – Exhaust Vent Termination (Sample No. 04-06-M0278-1).....9
Figure 3 – Mid-Efficiency Furnace 'Type B' Vent Configuration (Sample No. 04-06-M0278-2).....10
Figure 4 – Barometric Damper Location (Sample No. 04-06-M0278-2).....10
Figure 5 – Power venter Exhaust Terminal (Sample No. 04-06-M0278-2)10
Figure 6 – Water Heater Vent Configuration (Sample No. 04-06-M0278-4)11
Figure 7 – Exhaust Terminal (Sample No. 04-06-M0278-4)11
Figure 8 – High Efficiency Furnace Vent Configuration (Sample No. 04-06-M0278-5)12
Figure 9 – Exhaust Vent Termination (Sample No. 04-06-M0278-5).....12
Figure 10 – High Efficiency Furnace Vent Configuration (Sample No. 04-06-M0278-6)13
Figure 11 – High Efficiency Furnace Combustion Air Intake (Sample No. 04-06-M0278-6).....13
Figure 12 – Fireplace Insert Vent Termination (Sample No. 04-06-M0278-7)14
Figure 13 – Fireplace Insert Vent Configuration Outside Test Room (Sample No. 04-06-M0278-7).....14
Figure 14 – Zero Clearance Fireplace In Operation (Sample No. 04-06-M0278-8)15
Figure 15 – Zero Clearance Fireplace Vent Configuration (Sample No. 04-06-M0278-8)16
Figure 16 – Zero Clearance Fireplace Vent Termination (Sample No. 04-06-M0278-8).....16
Figure 17 – Static Leakage Test Set-Up 'Type B' Vent System (Sample No. 04-06-M0278-2)17
Figure 18 – Heating Module Leakage Test Set-Up (Sample No. 04-06-M0278-5)18
Figure 19 – Heating Module Leakage Test Set-Up (Sample No. 04-06-M0278-6)18
Figure 20 – Air Intake and Exhaust Connections (connections sealed) (Sample No. 04-06-M0278-7)19
Figure 21 – Heating Module Leakage Test Set-Up (Sample No. 04-06-M0278-8)19
Figure 22 – Concentric Vent Connection (exhaust duct sealed) (Sample No. 04-06-M0278-8)19

LIST OF TEST DATA SHEETS (APPENDIX B)

1. Transient Spillage Test at 50 Pa. Depressurization (Sample No. 04-06-M0278-1)..... B1
2. Transient Spillage Test at 50 Pa. Depressurization (Sample No. 04-06-M0278-2) Test #1 B2
3. Transient Spillage Test at 50 Pa. Depressurization (Sample No. 04-06-M0278-2) Test #2 B3
4. Transient Spillage Test at 50 Pa. Depressurization (Sample No. 04-06-M0278-4) Test #1 B4
5. Transient Spillage Test at 50 Pa. Depressurization (Sample No. 04-06-M0278-4) Test #2 B5
6. Transient Spillage Test at 50 Pa. Depressurization (Sample No. 04-06-M0278-5)..... B6
7. Transient Spillage Test at 50 Pa. Depressurization (Sample No. 04-06-M0278-6)..... B7
8. Transient Spillage Test at 50 Pa. Depressurization (Sample No. 04-06-M0278-7) Test #1 B8
9. Transient Spillage Test at 50 Pa. Depressurization (Sample No. 04-06-M0278-7) Test #2 B9
10. Transient Spillage Test at 20 Pa. Depressurization (Sample No. 04-06-M0278-7)..... B10
11. Transient Spillage Test at 5 Pa. Depressurization (Sample No. 04-06-M0278-7)..... B11
12. Transient Spillage Test at 50 Pa. Depressurization (Sample No. 04-06-M0278-8)..... B12

1.0 INTRODUCTION

Interest has been expressed in the development of a test procedure to determine the level of spillage of combustion products during start-up; operation and shutdown of a gas fired appliance when operating in a depressurized environment.

Bodycote Materials Testing Canada Inc. (BMTC) was contracted by Natural Resources Canada (NRCan) to conduct laboratory testing to assess a proposed test procedure to address this issue. NRCan’s work was supported by Canada Mortgage and Housing Corporation (CMHC).

This report is focused on a new ‘*transient spillage test*’ that can be used to evaluate the performance of a wide range of residential combustion equipment. It can be used:

- for evaluating combustion equipment that transfers heat directly to air such as furnaces and those that transfer heat directly to water such as boilers and water heaters
- to capture potential start-up and shut-down issues
- to evaluate air heating appliances without requiring any precision laboratory cooling equipment

In order to evaluate the proposed transient spillage test procedure, BMTC was supplied with 7 gas-fired residential appliances and their approved venting systems. Upon receipt, each appliance was assigned a unique BMTC Sample Number. Descriptions of each appliance, together with their assigned Sample Numbers are detailed in Table 1.

Table 1 – Appliance Descriptions and Assigned BMTC Sample Numbers				
Appliance Type	Description	Maximum Rated Input		BMTC Sample Number
		Btu/h	kW	
Water Heater	Power Vent	36,000	10.5	04-06-M0278-1
Furnace	Mid-Efficiency	75,000	22	04-06-M0278-2
Water Heater	Power Vent	34,000	10	04-06-M0278-4
Furnace	High Efficiency	80,000	23.4	04-06-M0278-5
Furnace	High Efficiency	80,000	23.4	04-06-M0278-6
Fireplace	Direct Vent Insert	24,000	7	04-06-M0278-7
Fireplace	Direct Vent Zero Clearance	21,000	6.2	04-06-M0278-8

Prior to carrying out any depressurization spillage testing, testing was performed to determine the integrity of the respective appliance venting and combustion system with regard to leakage rates.

All appliances were tested using the transient spillage procedure. As a point of comparison, BMTC Sample Numbers 04-06-M0278-1 and 04-06-M0278-2 were also tested using an earlier ‘steady state’ version of the test protocol that has previously been applied to products that first heated water.

2.0 TEST METHODOLOGY

2.1 Depressurization Spillage - General Test Procedure

The appliance shall be set-up in a test room that is equipped with an exhaust fan with sufficient capacity to allow for depressurization of the room to 0.2" w.c. (50 Pa.) with the appliance operating at the manufacturers' maximum rated input.

The exhaust vent terminal and, if applicable, the combustion air inlet shall be installed through the wall of the test room to discharge the combustion products into the adjacent space and bring combustion air from the adjacent space. The test shall be performed with the maximum certified equivalent lengths of venting and shall be installed in accordance with the manufacturers' instructions.

The adjacent space shall be adequately ventilated to ensure that the combustion products do not contaminate the space. A supplemental gas-capture and exhaust apparatus may be used to remove the combustion products from the space adjacent to the test room, provided that the CO₂ content, vent temperature and flow of the combustion products in the appliance combustion venting system is not affected by the operation of the apparatus.

A sampling port shall be installed to monitor the CO₂ level inside the test room and shall be located at the entrance of the depressurization exhaust duct. The pressure inside the test room shall be monitored at a location determined by the test laboratory but within 3-ft. (1 m) of the appliance under test. The pressure shall be maintained within ± 0.01 " w.c. (± 2 Pa.) for the duration of the depressurization test by adjusting the flow through the test room exhaust fan. The airflow through the exhaust fan shall be measured and recorded throughout the test.

2.2 Transient Spillage Test Procedure

The appliance under test and the test room shall be set-up as outlined in Section 2.1. Using the test room exhaust fan the test room shall be depressurized to 0.2" w.c. (50 Pa.) and shall be maintained at this level for the duration of the test. The test room, adjacent space and combustion vent temperature shall be at equilibrium ambient conditions prior to the commencement of the test.

A gas meter reading shall be recorded immediately prior to initiating burner operation.

The CO₂ level in the test room and the test room exhaust fan flow shall be recorded on a time-step basis of 30 seconds.

Burner operation shall be terminated after 5 minutes of operation and a gas meter reading shall be recorded. Measurements shall continue for an additional 2 minutes after burner shutdown.

The CO₂ level in the adjacent space shall be recorded immediately following the test.

If the calculated cumulative spillage exceeds 2% with the test room depressurized to 0.2" w.c. (50 Pa.) additional tests shall be conducted to determine the depressurization pressure threshold

level. The test shall be repeated with the test room depressurized to 0.08" w.c. (20 Pa.) If the calculated cumulative spillage is still in excess of 2%, the test shall be repeated with the test room depressurized to 0.02" w.c. (5 Pa.).

2.2.1 Transient Spillage Calculations

Transient spillage is calculated and reported over the entire 7-minute test period. For each time interval, calculate the CO₂ leakage into the room from the measured exhaust flow during the interval multiplied by the increase in CO₂ from the background level. If the appliance draws combustion air (including air used for pre-purge and post-purge) from the depressurized test room, the volume of combustion air shall be determined by either direct measurement or by combustion analysis. The combustion air drawn from the test room is added to the measured exhaust flow for each time interval.

Sum the intervals over the 7 minutes to calculate the cumulative CO₂ that has been removed by the exhaust fan.

Add the amount of CO₂ that remains in the test room calculated from the volume of the test room and the change in CO₂ between the start and end of the test.

Calculate the spillage as total CO₂ leakage divided by the CO₂ produced by the burner during the test time.

The appliance passes the test if the CO₂ spillage calculated over the entire test period is under 2% of the CO₂ generated by the appliance during the cycle (5 minutes of burner operation). The final 2 minutes of monitoring are conducted to observe the effects of shutdown spillage.

2.2.2 Steady State Depressurization Spillage Test Procedure

The appliance under test and the test room shall be set-up as outlined in Section 2.1. A load shall be imposed on the appliance to cause the burner to operate. The load shall be adjusted as necessary to maintain steady firing of the burner system at the maximum rated input for the duration of the test. Using the test room exhaust fan the test room shall be depressurized to 0.2" w.c. (50 Pa.). This level of depressurization shall be maintained for the duration of the test.

The CO₂ levels in the test room and the adjacent space shall be monitored during the test. The test shall be continued until steady state is obtained. Steady state shall be acceptable when the firing rate, net vent gas temperature, vent CO₂, test room CO₂, adjacent area CO₂ and test room exhaust fan flow do not vary by more than ±2% for three sets of readings taken over a fifteen minute period.

If the calculated spillage exceeds 2% with the test room depressurized to 0.2" w.c. (50 Pa.), the test shall be repeated with the test room depressurized successively by 0.12" w.c. (30 Pa.), 0.08" w.c. (20 Pa.), 0.04" w.c. (10 Pa.) and 0.02" w.c. (5 Pa.) until the calculated spillage is under 2%.

2.2.3 Steady State Depressurization Spillage Calculations

The CO₂ volume leakage from the appliance into the test room shall be calculated in CFM as follows:

$$\text{Leakage} = (\text{CO}_2 \text{ (test room)} - \text{CO}_2 \text{ (adjacent space)}) * \text{Exhaust Fan Flow (including combustion air from room if applicable)} * \text{Scaling Factor}$$

[The scaling factor is required to convert the concentration units of CO₂ to a decimal fraction and thereby calculate the leakage in SCFM]

The CO₂ generated by the combustion process, in SCFM shall be determined as follows:

$$\text{CO}_2 \text{ generated by the appliance burner} = \text{Input rate (Btu/h)/1000} * 0.0167 \text{ SCFM/1000 Btu/h}$$

$$\text{Spillage} = \text{Leakage} / \text{CO}_2 \text{ generated by the appliance burner}$$

2.3 Static Leakage Test Procedure

The static leakage test procedure that was used in this project to evaluate leakage of appliance vents and components is based on vent leakage tests that are included in existing test codes for gas-fired appliances. Vent leakage tests are normally intended for use only with direct vent appliances.

For this project the static leakage test was performed at a pressure of 0.1” w.c. (25 Pa.) as follows:

The component of interest shall be sealed at the point at which they would normally be connected to the vent and air intake terminals. The sealing means shall incorporate fittings suitable for introducing air to the specimen and shall include provisions to determine the air static pressure.

The internal static pressure in each section shall be determined using a pressure measurement instrument with measurement accuracy of at least 0.01” w.c. (2.5 Pa.).

A suitable supply of clean air shall be introduced into the specimen through a calibrated metering device. The air supply into the specimen shall be adjusted to produce an internal air pressure of 0.1” w.c. (25 Pa.), and the air flow rate required to produce this pressure shall be recorded as the section leakage (in cubic feet per hour).

2.3.1 Static Leakage Calculations

The airflow required to maintain the pressure of the test specimen at 0.1”w.c. (25 Pa.) shall be reported. The maximum allowable static leakage for each test specimen, corresponding with 2% leakage at the rated appliance input shall also be reported. The static leakage corresponding with 2% leakage shall be determined as follows:

$$L_C = 0.02 * 15 * I$$

Where:

L_C is the leakage rate in ft^3/h corresponding with 2% leakage.

The factor 15 is based on the formation of approximately 15 ft^3 combustion products (including 50% excess air) per 1000 Btu/h input.

I is the appliance burner input rate (in thousands of Btu/h)

3.0 TRANSIENT DEPRESSURIZATION SPILLAGE TEST SET-UP

All depressurization spillage tests were conducted using a supplemental gas-capture hood and exhaust system to remove the combustion products from the space adjacent to the test room.

The same procedure was used for setting up the steady state testing.

3.1 Sample Number 04-06-M0278-1 – Power Vented Water Heater

The power vented water heater was installed in the test room and set-up in accordance with the manufacturers' instructions. The appliance had a rated input of 36,000 Btu/h (10.5 kW) and incorporated an intermittent pilot and electronic ignition system. Venting requirements, as specified by the manufacturer comprised 2" ABS pipe and fittings. The maximum specified exhaust vent length of 60 equivalent feet was installed. The vent was terminated outside of the test room using a 90° terminal elbow supplied with the unit. The water heater utilized air from inside the test room for combustion and for the dilution of the exhaust products prior to entering the venting system. Photographs of the set-up are shown in Figures 1 and 2.




Figure 1 – Water Heater Vent Configuration
Sample No. 04-06-M0278-1



Figure 2 – Exhaust Vent Termination
Sample No. 04-06-M0278-1

3.2 Sample Number 04-06-M0278-2 – Mid-Efficiency Furnace

This induced draft mid-efficiency furnace is certified as a Category I appliance, and is approved as a fan- assisted negative pressure vent appliance. The furnace had a rated input of 75,000 Btu/h (22 kW) and incorporated an intermittent pilot and electronic ignition system.

In order to accommodate the sidewall venting requirement for installation in the BMTC test room, an accessory kit, specified by the manufacturer was purchased. The kit, comprised a sidewall power venter, a barometric damper and associated controls. It was installed and the supplemental control system was integrated with the furnace controls in accordance with the instructions.

The venting system comprised 4” double-wall ‘Type B’ vent and the maximum equivalent length of 35 feet, as specified in the installation instructions was installed. The furnace utilized air from inside the test room for combustion. Photographs of the set-up are shown in Figures 3 to 5.



Figure 3 – Mid-Efficiency Furnace
'Type B' Vent Configuration
Sample No. 04-06-M0278-2



Figure 4 – Barometric Damper Location
Sample No. 04-06-M0278-2



Figure 5 – Power Venter Exhaust Terminal
Sample No. 04-06-M0278-2

3.3 Sample Number 04-06-M0278-4 – Power Vented Water Heater

The power vented water heater was installed in the test room and set-up in accordance with the manufacturers’ instructions. The appliance had a rated input of 34,000 Btu/h (10 kW) and incorporated an intermittent pilot and electronic ignition system. Venting requirements, as specified by the manufacturer comprised 2” ABS pipe and fittings. The maximum specified exhaust vent length of 50 equivalent feet was installed. The vent was terminated outside of the test room using a 90° terminal elbow supplied with the unit. The water heater utilized air from inside the test room for combustion and for the dilution of the exhaust products prior to entering the venting system. Photographs of the set-up are shown in Figures 6 and 7.




Figure 6 – Water Heater Vent Configuration
Sample No. 04-06-M0278-4



Figure 7 – Exhaust Terminal
Sample No. 04-06-M0278-4

3.4 Sample Number 04-06-M0278-5 – High Efficiency Furnace

The high efficiency condensing furnace was installed in the test room and set-up in accordance with the manufacturers’ instructions. The furnace had a rated input of 80,000 Btu/h (23.4 kW) and incorporated an intermittent pilot and electronic ignition system. The manufacturers’ installation requirements specify that the furnace can be installed as a direct vent or non-direct vent system.

When installed as a direct vent system, combustion air is supplied from outside the building envelope and exhaust products are discharged to outdoors. A non-direct venting system would utilize indoor air for combustion while venting the combustion products outdoors.

For the requirements of this testing, a non-direct venting system was installed. 60 equivalent feet of 2” ABS pipe, the maximum length specified by the manufacturer was installed from the exhaust of the furnace, terminating outside of the test room. Air from inside the test room was used for combustion. Photographs of the set-up are shown in Figures 8 and 9.



**Figure 8 – High Efficiency Furnace Vent Configuration
Sample No. 04-06-M278-5**



**Figure 9 – Exhaust Vent Termination
Sample No. 04-06-M278-5**

3.5 Sample Number 04-06-M0278-6 – High Efficiency Furnace

The high efficiency condensing furnace was installed in the test room and set-up in accordance with the manufacturers’ instructions. The furnace had a rated input of 80,000 Btu/h (23.4 kW) and incorporated an intermittent pilot and electronic ignition system. The manufacturers’ installation requirements specify that the furnace can be installed as a direct vent or non-direct vent system.

When installed as a direct vent system, combustion air is supplied from outside the building envelope and exhaust products are discharged to outdoors. A non-direct venting system would utilize indoor air for combustion while venting the combustion products outdoors.

For the requirements of this testing, a non-direct venting system was installed. In compliance with the manufacturers’ specifications, the maximum vent length of 30 feet of 2” ABS pipe plus 5, 90° elbows was installed from the exhaust of the furnace, terminating outside of the test room. To comply with the manufacturers’ requirements for a non-direct vent system, a 9” length of ABS pipe and a 90° elbow were installed on the combustion air intake of the furnace. Two perforated disks, supplied with the furnace were positioned in this elbow as per the installation requirements. Air from inside the test room was used for combustion. Photographs of the set-up are shown in Figures 10 and 11.



Figure 10 - High Efficiency Furnace Vent Configuration
Sample No. 04-06-M278-6



Figure 11 - High Efficiency Furnace Vent Configuration
Showing Combustion Air Intake
Sample No. 04-06-M278-6

3.6 Sample Number 04-06-M0278-7 – Direct Vent Fireplace Insert


This fireplace is designed for installation as a retrofit for an existing solid fuel fireplace cavity. The unit supplied had a maximum rated input of 24,000 Btu/h (7 kW) and incorporated a standing pilot, having an input of approximately 1,500 Btu/h and a manually operated piezo ignition system. The appliance was equipped with an integral variable speed blower for air distribution. The blower was activated using a temperature sensing device within the fireplace enclosure.

Being a direct vent system, combustion air is supplied from outside the building envelope and exhaust products are discharged to outdoors.

The fireplace was installed in the test room and set-up in accordance with the manufacturers’ instructions. Two 3” diameter double-ply flexible aluminum pipes, one for combustion air and one for exhaust products were connected to the fireplace using high temperature silicone sealant. The flexible pipes were routed through the side wall of the test room and extended vertically, terminating at the vent terminal supplied by the manufacturer. While the extended length of the flexible pipes was specified as 35 feet each, limitations of the test area restricted this length to approximately 20 feet each. Photographs of the vent set-up are shown in Figures 12 and 13.



**Figure 12 – Fireplace Insert Vent Termination
Sample No. 04-06-M0278-7**



**Figure 13 – Fireplace Insert Vent Configuration
Outside Test Room
Sample No. 04-06-M0278-7**

3.7 Sample Number 04-06-M0278-8 – Direct Vent Zero Clearance Fireplace

This type of fireplace is designed for installation where there is no existing fireplace, typically during new home construction and requires no clearance to combustible materials. The supplied fireplace had a rated input of 21,000 Btu/h (6.2 kW) and incorporated a standing pilot, having an input of approximately 1,100 Btu/h and a manually operated piezo ignition system.

Being a direct vent system, combustion air is supplied from outside the building envelope and exhaust products are discharged to outdoors.

The fireplace was installed in the test room and set-up in accordance with the manufacturers' instructions. The venting for this unit utilized a concentric double-ply flexible aluminum pipe system. A 4" diameter inner pipe was used to vent the exhaust products, while a 7" diameter outer pipe provided the combustion air. Spring type spacers installed on the 4" diameter pipe acted to maintain an annular separation between the two pipes.

The concentric vent system was connected to the fireplace using high temperature silicone sealant in accordance with the manufacturers' instructions. The vent system was extended vertically for approximately 4 feet and horizontally for 8 feet, terminating at the side-wall vent terminal supplied by the manufacturer. Photographs of the set-up are shown in Figures 14 to 16.



Figure 14 –Zero Clearance Fireplace In Operation
Sample No. 04-06-M0278-8




Figure 15 – Zero Clearance Fireplace Vent Configuration
Sample No. 04-06-M0278-8



Figure 16 – Zero Clearance Fireplace
Vent Termination
Sample No. 04-06-M0278-8

4.0 LEAKAGE TESTING

The leakage test methodology outlined in Section 2.4 was developed as a requirement for the éKOCOMFORT™ AIMS evaluation program to determine the integrity of the venting and combustion modules of these integrated units. The procedure was developed primarily for direct vent appliances that utilize outdoor air for combustion and vent the combustion products outdoors.

The configuration of the appliances supplied for the present evaluation and the types of venting specified was such that not all of the test procedures were applicable.

4.1 Sample Numbers 04-06-M278-1 and 04-06-M278-4 – Power Vented Water Heaters

The two water heaters supplied were both power vented units that utilized indoor air for combustion and Schedule 40 ABS pipe to vent the combustion products to outdoors. Indoor air was also used by both appliances to reduce the temperature of the combustion products to acceptable levels prior to entering the ABS exhaust vent. Discussions between BMTC and NRCan concluded that vent leakage testing on these two venting systems was not required, as the integrity of the ABS vent pipe material was deemed to be such that no leakage would occur.

4.2 Sample Number 04-06-M278-2 – Mid Efficiency Furnace

The induced draft mid-efficiency furnace supplied utilized indoor air for combustion and was installed using ‘Type B’ vent to exhaust the combustion products.

As discussed earlier, a retrofit kit including a power venter and barometric damper was installed to accommodate side wall venting. The power venter, barometric damper and the Tee fitting that was used for installation of the damper were removed from the system prior to conducting the leakage test on the exhaust vent.

The opening used to accommodate the barometric damper was sealed and both ends of the vent were sealed. Fittings were incorporated to allow for the introduction of air and for the measurement of static pressure. A metering device was installed to measure the air flow rate. Clean air was introduced into the system and the flow rate was adjusted to provide a static pressure of 0.1” w.c. (25 Pa.). The air flow rate required to maintain this static pressure was recorded. A photograph of the test set-up is shown in Figure 17.



Figure 17 – Static Leakage Test Set-up
‘Type B’ Vent System
Sample No. 04-06-M0278-2

4.3 Sample Numbers 04-06-M278-5 and 04-06-M278-6 – High Efficiency Furnaces

As with the power vented water heaters, a similar situation was evident with the two high efficiency furnaces submitted for evaluation. Both units were tested as “one-pipe” non-direct vent units and therefore utilized indoor air for combustion. ABS pipe was used on both furnaces for the venting of combustion products. Again, it was concluded that performing leakage testing on these vents would be of no benefit.

As both furnaces had the option of being installed as direct vent systems, it was considered prudent to perform leakage testing on the heating module (combustion chamber and heat exchanger) assemblies of these units.

Leakage testing on both high efficiency furnaces was performed by sealing the combustion air inlet and exhaust products outlet connections at the furnace. Fittings were incorporated to allow for the introduction of air and for the measurement of static pressure. A metering device was installed to measure the air flow rate. Clean air was introduced into the system and the flow rate was adjusted to provide a static pressure of 0.1” w.c. (25 Pa.). The air flow rate required to maintain this static pressure was recorded. Photographs of the test set-up for each furnace are shown in Figures 18 and 19.



Figure 18 – Heating Module Leakage Test Set-up
Sample No. 04-06-M278-5



Figure 19 – Heating Module Leakage Test Set-up
Sample No. 04-06-M278-6

4.4 Sample Numbers 04-06-M278-7 and 04-06-M278-8 – Direct Vent Fireplaces

Both of the fireplaces supplied were direct vent appliances, utilizing outdoor air for combustion and exhausting the combustion products to outdoors. The venting systems for both units comprised seamless double ply flexible aluminum pipe. As with the ABS vent system used on the power vented water heaters and high efficiency furnaces, it was concluded that performing leakage testing on these vents would be of no benefit. As such, leakage testing was limited to the heating module (combustion chamber and heat exchanger) assemblies.

The combustion air inlet and exhaust products outlet connections were sealed at the fireplace. . Fittings were incorporated to allow for the introduction of air and for the measurement of static pressure. A metering device was installed to measure the air flow rate. Clean air was introduced into the system and the flow rate was adjusted to provide a static pressure of 0.1” w.c. (25 Pa.). The air flow rate required to maintain this static pressure was recorded. Photographs of the test set-up are shown in Figures 20 to 22.



Figure 20 – Air Intake and Exhaust Connections
(Shown with connections sealed)
Sample No. 04-06-M278-7



Figure 21 – Heating Module Leakage Test Set-up
Sample No. 04-06-M278-8



Figure 22 – Concentric Vent Connection
(Shown with exhaust duct sealed)
Sample No. 04-06-M278-8

5.0 TEST RESULTS

The results of the testing performed are detailed below. A summary of the test results is presented in Table 4.

Details of equipment and instrumentation used throughout the testing are shown in Appendix A.

5.1 Transient Spillage Test Results

The data recorded during the transient spillage testing is presented in Appendix B.

5.1.1 Sample Number 04-06-M0278-1 – Power Vented Water Heater

- Base test room CO₂ = 430 ppm
- Base adjacent space CO₂ = 422 ppm

- Room Static Pressure = -0.2” w.c. (-50 Pa)
- Room Exhaust Fan Flow = 261 scfm (123 l/s)
- Appliance Exhaust Flow = 21 scfm (10 l/s)

- Room CO₂ at start of test = 433 ppm
- Room CO₂ at end of test = 443 ppm
- Volume of test room = 1578 ft³

$$\text{Transient spillage} = (CO_2 \text{ in test room at end of test} + \text{Cumulative } CO_2 \text{ removed}) / CO_2 \text{ generated}$$

Where:

$$\begin{aligned} &CO_2 \text{ remaining in test room at end of 7 minute test} \\ &= ((\text{Room } CO_2 \text{ at end of test} - \text{Room } CO_2 \text{ at start of test}) * \text{Scaling Factor}) * \text{Volume of Test Room} \\ &\quad (\text{Where the Scaling Factor converts } CO_2 \text{ concentrations in ppm to a decimal fraction}) \\ &= ((443 - 433) * 0.000001) * 1578 \\ &= 0.016 \text{ ft}^3 \end{aligned}$$

$$\begin{aligned} &CO_2 \text{ removed from test room per time interval} \\ &= (CO_2 \text{ (test room)} - CO_2 \text{ (adjacent space)}) * (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Flow}) * (\text{Scaling Factor}) \end{aligned}$$

$$\begin{aligned} &\text{Cumulative } CO_2 \text{ removed from test room} \\ &= \text{Cumulative Sum of } CO_2 \text{ removed from test room per time interval} \\ &= 0.0175 \text{ ft}^3 \end{aligned}$$

$$\begin{aligned} &CO_2 \text{ generated by appliance during 5 minute burner operation} \\ &= (\text{Input Rate [Btu/h]/1000}) * (0.0167 \text{ [SCFM]/1000 [Btu/h]}) * \text{Time [minutes]} \\ &= ((36,000 * 0.0167) / 1000) * 5 \\ &= 3 \text{ ft}^3 \end{aligned}$$

$$\text{Transient spillage} = (0.016 + 0.0175) / 3 = 0.0112$$

Transient Spillage at 0.2” w.c. (50 Pa) depressurization = 1.1%

5.1.2 Sample Number 04-06-M0278-2 – Mid-Efficiency Furnace Test #1

Base test room CO₂ = 440 ppm
Base adjacent space CO₂ = 440 ppm

Room Static Pressure = -0.2” w.c. (-50 Pa)
Room Exhaust Fan Flow = 267 scfm (126 l/s)
Appliance Exhaust Flow = 18 scfm (9 l/s)

Room CO₂ at start of test = 441 ppm
Room CO₂ at end of test = 452 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = 0.018 ft³
Cumulative CO₂ removed from test room = 0.0046 ft³
CO₂ generated by appliance during 5 minute burner operation = 6.26 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient spillage at 0.2” w.c. (50 Pa) depressurization = 0.4%

5.1.2.1 Sample Number 04-06-M0278-2 – Mid-Efficiency Furnace Test #2

Test performed with increased flow at supplemental gas-capture hood in order to minimize contamination of adjacent area.

Base test room CO₂ = 442 ppm
Base adjacent space CO₂ = 423 ppm

Room Static Pressure = -0.2” w.c. (-50 Pa)
Room Exhaust Fan Flow = 282 scfm (133 l/s)
Appliance Exhaust Flow = 18 scfm (9 l/s)

Room CO₂ at start of test = 442 ppm
Room CO₂ at end of test = 448 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = 0.01 ft³
Cumulative CO₂ removed from test room = 0.0003 ft³
CO₂ generated by appliance during 5 minute burner operation = 6.3 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient spillage at 0.2” w.c. (50 Pa) depressurization = 0.2%

5.1.3 Sample Number 04-06-M0278-4 – Power Vented Water Heater Test #1

Base test room CO₂ = 414 ppm
Base adjacent space CO₂ = 426 ppm

Room Static Pressure = -0.2” w.c. (-50 Pa)
Room Exhaust Fan Flow = 248 scfm (117 l/s)
Appliance Exhaust Flow = 31 scfm (14 l/s)

Room CO₂ at start of test = 413 ppm
Room CO₂ at end of test = 433 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = 0.032 ft³
Cumulative CO₂ removed from test room = 0.0107 ft³
CO₂ generated by appliance during 5 minute burner operation = 2.75 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient Spillage at 0.2” w.c. (50 Pa) depressurization = 1.6%

5.1.3.1 Sample Number 04-06-M0278-4 – Power Vented Water Heater Test #2

Test performed with water heater exhaust venting directly into the test room. This test was conducted to validate the test procedure and to establish the calculated spillage. Ideally, the resultant spillage should equal 100% under this test condition.

Base test room CO₂ = 454 ppm
Base adjacent space CO₂ = 441 ppm

Room Static Pressure = -0.2” w.c. (-50 Pa)
Room Exhaust Fan Flow = 269 scfm (127 l/s)
Appliance Exhaust Flow = 31 scfm (14 l/s)

Room CO₂ at start of test = 440 ppm
Room CO₂ at end of test = 1235 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = 1.255 ft³
Cumulative CO₂ removed from test room = 1.087 ft³
CO₂ generated by appliance during 5 minute burner operation = 2.74 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient spillage at 0.2” w.c. (50 Pa) depressurization = 85%

5.1.4 Sample Number 04-06-M0278-5 – High-Efficiency Furnace

Base test room CO₂ = 446 ppm
Base adjacent space CO₂ = 439 ppm

Room Static Pressure = -0.2” w.c. (-50 Pa)
Room Exhaust Fan Flow = 279 scfm (132 l/s)
Appliance Exhaust Flow = 20 scfm (9.5 l/s)

Room CO₂ at start of test = 447 ppm
Room CO₂ at end of test = 453 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = 0.009 ft³
Cumulative CO₂ removed from test room = -0.0062 ft³
CO₂ generated by appliance during 5 minute burner operation = 6.05 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient spillage at 0.2” w.c. (50 Pa) depressurization = 0.05%

5.1.5 Sample Number 04-06-M0278-6 – High-Efficiency Furnace

Base test room CO₂ = 423 ppm
Base adjacent space CO₂ = 436 ppm

Room Static Pressure = -0.2” w.c. (-50 Pa)
Room Exhaust Fan Flow = 295 scfm (139 l/s)
Appliance Exhaust Flow = 24 scfm (11 l/s)

Room CO₂ at start of test = 426 ppm
Room CO₂ at end of test = 426 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = -0.001 ft³
Cumulative CO₂ removed from test room = 0.0092 ft³
CO₂ generated by appliance during 5 minute burner operation = 6.21 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient Spillage at 0.2” w.c. (50 Pa) depressurization = 0.14%

5.1.6 Sample Number 04-06-M0278-7 – Direct Vent Fireplace Insert – Test #1

Base test room CO₂ = 443 ppm
Base adjacent space CO₂ = 409 ppm

Room Static Pressure = -0.2" w.c. (-50 Pa)
Room Exhaust Fan Flow = 274 scfm (129 l/s)
Appliance Exhaust Flow = 9 scfm (4 l/s)

Room CO₂ at start of test = 443 ppm
Room CO₂ at end of test = 548 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = 0.166 ft³
Cumulative CO₂ removed from test room = 0.1128 ft³
CO₂ generated by appliance during 5 minute burner operation = 2.1 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient spillage at 0.2" w.c. (50 Pa) depressurization = 13.3%

5.1.6.1 Sample Number 04-06-M0278-7 – Direct Vent Fireplace Insert – Test #2

Repeat of Test #1. Additional circulating fan installed in test room to improve mixing and ensure uniform environment.

Base test room CO₂ = 450 ppm
Base adjacent space CO₂ = 411 ppm

Room Static Pressure = -0.2" w.c. (-50 Pa)
Room Exhaust Fan Flow = 266 scfm (125 l/s)
Appliance Exhaust Flow = 9 scfm (4 l/s)

Room CO₂ at start of test = 456 ppm
Room CO₂ at end of test = 531 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = 0.118 ft³
Cumulative CO₂ removed from test room = 0.1467 ft³
CO₂ generated by appliance during 5 minute burner operation = 2.07 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient spillage at 0.2" w.c. (50 Pa) depressurization = 12.8%

5.1.6.2 Sample Number 04-06-M0278-7 – Direct Vent Fireplace Insert – Test #3

Test room depressurization at 0.08” w.c. (20 Pa.)

Base test room CO₂ = 455 ppm
Base adjacent space CO₂ = 421 ppm

Room Static Pressure = -0.08” w.c. (-20 Pa)
Room Exhaust Fan Flow = 139 scfm (66 l/s)
Appliance Exhaust Flow = 9 scfm (4 l/s)

Room CO₂ at start of test = 455 ppm
Room CO₂ at end of test = 482 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = 0.044 ft³
Cumulative CO₂ removed from test room = 0.0299 ft³
CO₂ generated by appliance during 5 minute burner operation = 2.09 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient Spillage at 0.08” w.c. (20 Pa) depressurization = 3.5%

5.1.6.3 Sample Number 04-06-M0278-7 – Direct Vent Fireplace Insert – Test #4

Test room depressurization at 0.02” w.c. (5 Pa.)

Base test room CO₂ = 441 ppm
Base adjacent space CO₂ = 412 ppm

Room Static Pressure = -0.02” w.c. (-5 Pa)
Room Exhaust Fan Flow = 55 scfm (26 l/s)
Appliance Exhaust Flow = 9 scfm (4 l/s)

Room CO₂ at start of test = 441 ppm
Room CO₂ at end of test = 442 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = 0.001 ft³
Cumulative CO₂ removed from test room = -0.0007 ft³
CO₂ generated by appliance during 5 minute burner operation = 2.08 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient spillage at 0.02” w.c. (5 Pa) depressurization = 0.01%

5.1.7 Sample Number 04-06-M0278-8 – Direct Vent Zero Clearance Fireplace

Base test room CO₂ = 414 ppm
Base adjacent space CO₂ = 409 ppm

Room Static Pressure = -0.2" w.c. (-50 Pa)
Room Exhaust Fan Flow = 282 scfm (133 l/s)
Appliance Exhaust Flow = 15 scfm (7 l/s)

Room CO₂ at start of test = 415 ppm
Room CO₂ at end of test = 412 ppm
Volume of test room = 1578 ft³

CO₂ remaining in test room at end of 7 minute test = 0.005 ft³
Cumulative CO₂ removed from test room = 0.0086 ft³
CO₂ generated by appliance during 5 minute burner operation = 1.95 ft³

Transient spillage = (CO₂ remaining in test room at end of test + Cumulative CO₂ removed) / CO₂ generated

Transient spillage at 0.2" w.c. (50 Pa) depressurization = 0.7%

5.2 Steady State Depressurization Spillage Test Results

5.2.1 Sample Number 04-06-M0278-1 – Power Vented Water Heater

Table 2 – Steady State Depressurization Spillage Test Data – Sample No. 04-06-M0278-1					
Time	T_{vent}		CO₂ (vent) (%)	CO₂ (test room) (ppm)	CO₂ (adjacent space) (ppm)
	(°F)	(°C)			
15:10	123.0	50.6	3.2	504	489
15:15	122.9	50.5	3.2	507	487
15:20	122.9	50.5	3.2	503	484
15:25	122.9	50.5	3.2	500	486

The maximum variance of T_{exhaust}, CO₂ (exhaust), CO₂ (test room) and CO₂ (adjacent space) did not exceed 2% during the test period.

Base test room CO₂ = 508 ppm
Base adjacent space CO₂ = 488 ppm

Average fuel input rate = 37,299 Btu/h
Room Static Pressure = -0.2” w.c. (-50 Pa)
Room Exhaust Fan Flow = 276 scfm (130 l/s)
Appliance Exhaust Flow = 21 scfm (10 l/s)

Spillage = Leakage / CO₂ generated by the unit.

Where:

*Leakage = (CO₂ (test room) – CO₂ (adjacent space)) * (Exhaust Fan Flow + Appliance Exhaust Flow) * (Scaling Factor)*

(Where the Scaling Factor converts CO₂ concentrations in ppm to a decimal fraction)

CO₂ generated by the unit = (Input Rate [Btu/h]/1000) x (0.0167 [SCFM]/1000 [Btu/h])

The spillage from the appliance was calculated to be -0.1%.

5.2.2 Sample Number 04-06-M0278-2 – Mid-Efficiency Furnace

Table 3 – Steady State Depressurization Spillage Test Data – Sample No. 04-06-M278-2					
Time	T_{exhaust}		CO₂ (exhaust) (%)	CO₂ (test room) (ppm)	CO₂ (adjacent space) (ppm)
	(°F)	(°C)			
15:40	379.2	192.9	7.9	466	428
15:45	379.4	193.0	7.9	466	427
15:50	379.4	193.0	7.9	464	430
15:55	379.6	193.1	7.9	464	430

The maximum variance of T_{exhaust}, CO₂ (exhaust), CO₂ (test room) and CO₂ (adjacent space) did not exceed 2% during the test period.

Base test room CO₂ = 429 ppm
Base adjacent space CO₂ = 422 ppm

Average fuel input rate = 75,070 Btu/h
Room Static Pressure = -0.2” w.c. (-50 Pa)
Room Exhaust Fan Flow = 262 scfm (124 l/s)
Appliance Exhaust Flow = 18 scfm (9 l/s)

$$\text{Spillage} = \text{Leakage} / \text{CO}_2 \text{ generated by the unit.}$$

Where:

$$\text{Leakage} = (\text{CO}_2 \text{ (test room)} - \text{CO}_2 \text{ (adjacent space)}) * (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Flow}) * (\text{Scaling Factor})$$

(Where the Scaling Factor converts CO₂ concentrations in ppm to a decimal fraction)

$$\text{CO}_2 \text{ generated by the unit} = (\text{Input Rate [Btu/h]}/1000) \times (0.0167 \text{ [SCFM]}/1000 \text{ [Btu/h]})$$

The spillage from the appliance was calculated to be 0.6%.

5.3 Static Leakage Test Results

5.3.1 Sample Numbers 04-06-M0278-1 and 04-06-M0278-4 – Power Vented Water Heaters

No leakage testing was performed on these appliances as the integrity of the ABS vent pipe material was deemed to be such that no leakage would occur.

5.3.2 Sample Number 04-06-M0278-2 – Mid-Efficiency Furnace

Leakage testing was performed on the combustion exhaust vent.

The leakage rate recorded during the test was 186 cfh (87.8 l/min)

Leakage rate expressed as a percentage of the input rating (including 50% excess air)
 $= 186 / (15 * 75)$
 $= 16.5\%$

Corresponding leakage rate at 2% (L_C) $= 0.02 * 15 * 75$
 $= 22.5 \text{ cfh (10.6 l/min)}$

As this furnace is certified as a Category I appliance, the vent system operates under negative pressure. As such, subjecting this type of vent to a static leakage test is not applicable.

5.3.3 Sample Number 04-06-M0278-5 – High-Efficiency Furnace

Leakage testing was performed on the furnace heating module (combustion chamber/heat exchanger).

The leakage rate recorded during the test was 10.8 cfh (5.1 l/min)

Leakage rate expressed as a percentage of the input rating (including 50% excess air)
 $= 10.8 / (15 * 80)$
 $= 0.9\%$

Corresponding leakage rate at 2% (L_C) $= 0.02 * 15 * 80$
 $= 24 \text{ cfh (11.3 l/min)}$

5.3.4 Sample Number 04-06-M0278-6 – High-Efficiency Furnace

Leakage testing was performed on the furnace heating module (combustion chamber/heat exchanger).

The leakage rate recorded during the test was 9.5 cfh (4.5 l/min)

Leakage rate expressed as a percentage of the input rating (including 50% excess air)
 $= 9.5 / (15 * 80)$
 $= 0.8\%$

Corresponding leakage rate at 2% (L_C) $= 0.02 * 15 * 80$
 $= 24$ cfh (11.3 l/min)

5.3.5 Sample Number 04-06-M0278-7 – Direct Vent Fireplace Insert

Leakage testing was performed on the fireplace heating module (combustion chamber/heat exchanger).

The leakage rate recorded during the test was 6 cfh (2.9 l/min)

Leakage rate expressed as a percentage of the input rating (including 50% excess air)
 $= 6 / (15 * 24)$
 $= 1.7\%$

Corresponding leakage rate at 2% (L_C) $= 0.02 * 15 * 24$
 $= 7.2$ cfh (3.4 l/min)

5.3.6 Sample Number 04-06-M0278-8 – Direct Vent Zero Clearance Fireplace

Leakage testing was performed on the fireplace heating module (combustion chamber/heat exchanger).

The leakage rate recorded during the test was 4.7 cfh (2.2 l/min)

Leakage rate expressed as a percentage of the input rating (including 50% excess air)
 $= 4.7 / (15 * 21)$
 $= 1.5\%$

Corresponding leakage rate at 2% (L_C) $= 0.02 * 15 * 21$
 $= 6.3$ cfh (3 l/min)

Table 4 – Summary of Test Results

	Power Vented Water Heater 04-06-M278-1	Mid-Efficiency Furnace 04-06-M278-2	Power Vented Water Heater 04-06-M278-4	High Efficiency Furnace 04-06-M278-5	High Efficiency Furnace 04-06-M278-6	Direct Vent Fireplace Insert 04-06-M278-7	Direct Vent Zero Clearance Fireplace 04-06-M278-8
Maximum Rated Input (MBtu/h) (kW)	36 (10.5)	75 (22)	34 (10)	80 (23.4)	80 (23.4)	24 (7)	21 (6.2)
Maximum Equivalent Exhaust Vent Length (ft) (m)	60 (18)	35 (11)	50 (15)	60 (18)	55 (17)	35 (11)	12 (4) ¹
Maximum Equivalent Combustion Air Vent Length (ft) (m)	-	-	-	60 (18) ²	55 (17) ²	35 (11)	12 (4) ¹
Burner Pre-Purge Time (seconds)	15	15	15	60	45	0	0
Burner Post-Purge Time (seconds)	30	15	30	30	15	0	0
Transient Spillage at 0.2" w.c. (50 Pa) Depressurization (%)	1.1	0.4 / 0.2 ³	1.6	0.05	0.14	13.3 / 12.8 ⁴	0.7
Transient Spillage at 0.08" w.c. (20 Pa) Depressurization (%)	-	-	-	-	-	3.5	-
Transient Spillage at 0.02" w.c. (5 Pa) Depressurization (%)	-	-	-	-	-	0.01	-
Steady State Spillage at 0.2" w.c. (50 Pa) Depressurization (%)	-0.1	0.6	-	-	-	-	-
Static Leakage (cfh) (l/min)	-	186 (87.8) ⁵	-	10.8 (5.1) ⁶	9.5 (4.5) ⁶	6.0 (2.9) ⁶	4.7 (2.2) ⁶
Static Leakage (%) ⁷	-	16.5	-	0.9	0.8	1.7	1.5

1. Tested with 4 ft. (1.2 m) vertical, 8 ft. (2.4 m) horizontal venting installed.
2. Appliances tested as single pipe installations – combustion air vent not installed.
3. Reduction in calculated spillage from 0.4% to 0.2% after flow increased at supplemental gas-capture hood to minimize contamination of adjacent area.
4. Reduction in calculated spillage from 13.3% to 12.8% after installation of additional circulation fan in test room to improve mixing and ensure uniform environment.
5. Leakage testing conducted on exhaust vent only.
6. Leakage testing conducted on combustion chamber/heat exchanger only.
7. Leakage rate expressed as a percentage of the appliance input rating (including 50% excess air).

6.0 TESTING COMMENTS

Results of the transient combustion spillage tests performed show that 6 of the 7 appliances had a calculated spillage of less than 2% with the test room depressurized to 0.2" w.c. (50 Pa.) prior to the commencement of the testing.

The direct vent fireplace insert, had a spillage of 13.3% with the test room depressurized to 0.2" w.c. (50 Pa.). This test was repeated with an additional air circulation fan installed in the test room to provide additional mixing of the room environment. The repeated test resulted in a calculated spillage of 12.8%. This 4% reduction in spillage may be attributed to better mixing of the test room environment or, the level of repeatability of the test method. Additional tests were conducted on this appliance with the test room depressurized to 0.08" w.c. (20 Pa.) and 0.02" w.c. (5 Pa.), resulting in calculated spillage of 3.5% and 0.01% respectively.

During some of the transient spillage tests conducted, oscillations were apparent in the readings recorded from the analyser being used to monitor CO₂ concentrations in the adjacent area. The magnitudes of the oscillations were in the order of ± 15 ppm. Transient spillage for these tests was calculated using both the recorded values and an averaged value over the test period. In both cases the calculated spillage were in agreement. The spillage values reported are based on the average of the values recorded.

The -0.1% result reported for one of the steady state spillage tests may be attributed to a number of factors:

- The analysers used to monitor CO₂ concentrations in the test room and adjacent space have an accuracy of $\pm 1\%$ and $\pm 2\%$ of full scale respectively.
- Infiltration of ambient air from outside of the test room into the test room environment.
- Contamination of the adjacent space environment due to appliance exhaust products external influences beyond the control of the test personnel.
- Proper mixing of the environment inside the room.

These factors may also account for the value of 85% reported for the test in which the appliance was exhausted directly into the test room.

In order to minimize the above effects, the following steps were taken:

- Analysers were calibrated prior to commencement and at the completion of each test.
- All evident openings in the test room envelope were sealed.
- Flow in the supplemental exhaust products capture hood was increased to adequately vent the appliance exhaust products in order to minimize contamination of the adjacent space.
- Air circulation fans were operated in the test room to ensure proper mixing of the environment.


The static leakage test that was performed on the exhaust vent of the mid-efficiency furnace resulted in a reported leakage rate of 16.5% (expressed as a percentage of burner input rate (including 50% excess air)). As this furnace is certified as a Category I appliance, the vent

system operates under negative pressure. As such, subjecting this type of vent to a static leakage test is not applicable.


The static leakage test that was performed on the heating module of the direct vent fireplace insert resulted in a reported leakage rate of 1.7% (expressed as a percentage of burner input rate (including 50% excess air)). Based on an acceptable leakage rate of less than 2%, this appliance would satisfy the requirement. However, the transient spillage tests performed at 0.2" w.c. (50 Pa.) and 0.08" w.c. (20 Pa.) depressurization resulted in spillage of 12.8% and 3.5% respectively. Based on an acceptable spillage of less than 2%, this appliance would not satisfy the requirement.

The static leakage test is performed with the appliance not in operation. Conversely, the transient spillage test is performed with the appliance operating. It can be surmised that, with the appliance operating, expansion of sheet metal parts subjected to temperature differences could result in the separation of adjoining surfaces thereby allowing leakage of combustion products. If the leakage were such that combustion products enter the test room, the transient spillage test procedure would detect the elevated concentrations of CO₂ and identify any leakage as spillage.


Reported by:


Chris Runcieman, C.E.T.
Senior Technologist, Ext. 484
Building Performance Centre

Reported by:


Don Giannini, B.Tech, C.E.T.
Senior Technologist, Ext. 491
Building Performance Centre

Reviewed by:


David Bailey, P.Eng.
Operations Manager, Ext. 307
Engineering & Transportation

REGISTRATION

ISO 9002-1994 registered by QMI, Registration #001109

This report refers only to the particular samples, units, material, instrument, or other subject used and referred to in it, and is limited by the tests and/or analyses performed. Similar articles may not be of like quality, and other testing and/or analysis programs might be desirable and might give different results.

APPENDIX A

(1 Page)

Table 5 - Details of Equipment and Instrumentation Used

Device	Make	Model	MII Number	Full Scale Range(s)	Accuracy
CO ₂ Analyser	Beckman	865	B00335	2500/1000/500 ppm	±1% full scale
CO ₂ Analyser	Nova	PN300D	A09088	2000 ppm	±2% full scale
Laminar Flow Element	Meriam	50MC2-4	B00609	400 scfm (189 l/s)	±0.5%
Laminar Flow Element	Meriam	50MW20-1	A011554	7.5 scfm (3.5 l/s)	±0.5%
Pressure Transducer	Love	HM 28	B04244	10" w.c. (2.5 kPa)	±0.2% full
Pressure Transducer	Dwyer	477-1-FM	B04246	20" w.c. (5 kPa)	±0.5% full
Pressure Transducer	Baratron	2200A	A11647	1000 torr (133 kPa)	±0.5% full
Thermocouple	T Type	-	B02988	-	±2°F (±1.1°C)
Thermocouple	T Type	-	B02989	-	±2°F (±1.1°C)

APPENDIX B

(12 Pages)

Transient Spillage Test at 50 Pa. Depressurization

Sample No.: 04-06-M278-1
Client: NRCan
Test Date: 4/20/2004

$CO_2 \text{ leakage per time base interval} = (CO_2 \text{ (test room)} - CO_2 \text{ (adjacent room)}) \cdot (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Products Flow}) \cdot (\text{Scaling Factor})$

$CO_2 \text{ remaining in test room at end of test} = (CO_2 \text{ (test room end)} - CO_2 \text{ (test room start)}) \cdot (\text{Scaling Factor}) \cdot (\text{Test Room Volume})$

$CO_2 \text{ generated by appliance} = (\text{Input Rate (Btu/h)} / 1000) \cdot (0.0167 \text{ SCFM} / 1000 \text{ Btu/h})$


$\text{Spillage} = \text{Total } CO_2 \text{ Leakage} / CO_2 \text{ generated by appliance}$

	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	Post Purge	Inducer Blower Off		
Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO ₂ (test room, base) (ppm):	430	430	430	430	430	430	430	430	430	430	430	430	430	430
CO ₂ (adjacent room, base) (ppm):	422	422	422	422	422	422	422	422	422	422	422	422	422	422
CO ₂ (test room) (ppm):	433	431	434	437	439	438	439	441	445	447	448	445	446	443
CO ₂ (adjacent room) (ppm):	422	422	422	422	422	422	423	423	423	423	423	423	423	425
Exhaust Fan Flow (ACFM):	272.9	272.9	272.9	272.9	272.9	272.9	272.9	272.9	272.9	272.9	272.9	272.9	272.9	272.9
Exhaust Fan Flow (SCFM):	261.3	261.3	261.3	261.3	261.3	261.3	261.3	261.3	261.3	261.3	261.3	261.3	261.3	261.3
Vent CO ₂ concentration (%) ¹ :	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	21.5	21.5	21.5	21.5	21.5	21.5	21.5	21.5	21.5	21.5	20.9	0.0	0.0	0.0
Scaling Factor:	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06
∴ CO ₂ (depressurization) Leakage (ft ³) =	0.0003	0.0000	0.0005	0.0008	0.0012	0.0011	0.0011	0.0014	0.0018	0.0020	0.0024	0.0018	0.0018	0.0013

¹ Vent CO₂ concentration measured at vent terminal (appliance operating at steady state conditions)

² Total combustion products exhausted from test room (including excess air & dilution air)

Test Room CO₂ at end of 7 minute test = 443 ppm
 Test Room CO₂ at start of test = 433 ppm
 Volume of test room = 1578 ft³
 CO₂ remaining in test room at end of test = 0.016 ft³
 Total CO₂ removed from test room over 7 minute test period = 0.0175 ft³
 Total CO₂ leakage = 0.0337 ft³
 CO₂ Generated by appliance during 5 minute burner ON time = 3.006 ft³
 Spillage (Total CO₂ leakage/ Appliance CO₂) = 1.121%



Transient Spillage Test at 50 Pa. Depressurization

Sample No.: 04-06-M278-2
Client: NRCan
Test Date: 4/21/2004

$CO_2 \text{ leakage per time base interval} = (CO_2 \text{ (test room)} - CO_2 \text{ (adjacent room)}) \cdot (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Products Flow}) \cdot (\text{Scaling Factor})$

$CO_2 \text{ remaining in test room at end of test} = (CO_2 \text{ (test room end)} - CO_2 \text{ (test room start)}) \cdot (\text{Scaling Factor}) \cdot (\text{Test Room Volume})$

$CO_2 \text{ generated by appliance} = (\text{Input Rate (Btu/h)/1000}) \cdot (0.0167 \text{ SCFM/1000 Btu/h})$


$\text{Spillage} = \text{Total } CO_2 \text{ Leakage} / CO_2 \text{ generated by appliance}$

	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO ₂ (test room, base) (ppm):	440	440	440	440	440	440	440	440	440	440	440	440	440	440
CO ₂ (adjacent room, base) (ppm):	440	440	440	440	440	440	440	440	440	440	440	440	440	440
CO ₂ (test room) (ppm):	441	442	444	444	446	448	449	451	451	452	454	453	453	452
CO ₂ (adjacent room) (ppm):	438	438	437	438	440	441	446	451	459	455	452	450	448	452
Exhaust Fan Flow (ACFM):	277.4	277.4	277.4	277.4	277.4	277.4	277.4	277.4	277.4	277.4	277.4	277.4	277.4	277.4
Exhaust Fan Flow (SCFM):	267.4	267.4	267.4	267.4	267.4	267.4	267.4	267.4	267.4	267.4	267.4	267.4	267.4	267.4
Appliance CO ₂ concentration (%) ¹ :	8.0	8.0	8.0	8.0	8.0	8.0	8.0	8.0	8.0	8.0	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	18.1	18.1	18.1	18.1	18.1	18.1	18.1	18.1	18.1	18.1	16.7	0.0	0.0	0.0
Scaling Factor:	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06
∴ CO ₂ (depressurization) Leakage (ft ³) =	0.0004	0.0006	0.0008	0.0009	0.0009	0.0008	0.0004	-0.0001	-0.0012	-0.0004	0.0002	0.0005	0.0007	0.0001

¹ CO₂ concentration measured at appliance (appliance operating at steady state conditions)

² Total combustion products exhausted from test room (including excess air)

Test Room CO₂ at end of 7 minute test = 452 ppm
 Test Room CO₂ at start of test = 441 ppm
 Volume of test room = 1578 ft³
 CO₂ remaining in test room at end of test = 0.018 ft³
 Total CO₂ removed from test room over 7 minute test period = 0.0046 ft³
 Total CO₂ leakage = 0.0229 ft³
 CO₂ Generated by appliance during 5 minute burner ON time = 6.2625 ft³
 Spillage (Total CO₂ leakage/ Appliance CO₂) = 0.4%



Transient Spillage Test at 50 Pa. Depressurization

Sample No.: 04-06-M278-2
Client: NRCan
Test Date: 4/25/2004

Increased Flow at exhaust products capture hood in adjacent area

$$CO_2 \text{ leakage per time base interval} = (CO_2 \text{ (test room)} - CO_2 \text{ (adjacent room)}) \cdot (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Products Flow}) \cdot (\text{Scaling Factor})$$

$$CO_2 \text{ remaining in test room at end of test} = (CO_2 \text{ (test room end)} - CO_2 \text{ (test room start)}) \cdot (\text{Scaling Factor}) \cdot (\text{Test Room Volume})$$

$$CO_2 \text{ generated by appliance} = (\text{Input Rate (Btu/h)/1000}) \cdot (0.0167 \text{ SCFM/1000 Btu/h})$$


$$\text{Spillage} = \text{Total } CO_2 \text{ Leakage} / CO_2 \text{ generated by appliance}$$

	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	Post Purge 5.50	6.00	6.50	Power Vent Off 7.00
Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO ₂ (test room, base) (ppm):	442	442	442	442	442	442	442	442	442	442	442	442	442	442
CO ₂ (adjacent room, base) (ppm):	423	423	423	423	423	423	423	423	423	423	423	423	423	423
CO ₂ (test room) (ppm):	442	442	442	442	443	443	444	446	448	449	451	449	449	448
CO ₂ (adjacent room) (ppm):	423	423	423	423	424	426	429	426	427	427	429	429	431	431
Exhaust Fan Flow (ACFM):	291.3	291.3	291.3	291.3	291.3	291.3	291.3	291.3	291.3	291.3	291.3	291.3	291.3	291.3
Exhaust Fan Flow (SCFM):	281.9	281.9	281.9	281.9	281.9	281.9	281.9	281.9	281.9	281.9	281.9	281.9	281.9	281.9
Appliance CO ₂ concentration (%) ¹ :	8.0	8.0	8.0	8.0	8.0	8.0	8.0	8.0	8.0	8.0	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	18.1	18.1	18.1	18.1	18.1	18.1	18.1	18.1	18.1	18.1	16.7	0.0	0.0	0.0
Scaling Factor:	1E-06	1E-06	1E-06	1E-06	1E-06	1E-06	1E-06	1E-06	1E-06	1E-06	1E-06	1E-06	1E-06	1E-06
∴ CO ₂ (depressurization) Leakage (ft ³) =	0.0000	0.0000	0.0000	0.0001	0.0000	-0.0002	-0.0005	0.0001	0.0002	0.0005	0.0003	0.0002	-0.0001	-0.0003

¹ CO₂ concentration measured at appliance (appliance operating at steady state conditions)

² Total combustion products exhausted from test room (including excess air)

Test Room CO₂ at end of 7 minute test = 448 ppm
 Test Room CO₂ at start of test = 442 ppm
 Volume of test room = 1578 ft³
 CO₂ remaining in test room at end of test = 0.010 ft³
 Total CO₂ removed from test room over 7 minute test period = 0.0003 ft³
 Total CO₂ leakage = 0.0104 ft³
 CO₂ Generated by appliance during 5 minute burner ON time = 6.26 ft³
 Spillage (Total CO₂ leakage/ Appliance CO₂) = 0.2%



Transient Spillage Test at 50 Pa. Depressurization

Sample No.: 04-06-M278-4
Client: NRCan
Test Date: 5/3/2004

$CO_2 \text{ leakage per time base interval} = (CO_{2 \text{ (test room)}} - CO_{2 \text{ (adjacent room)}}) \cdot (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Products Flow}) \cdot (\text{Scaling Factor})$

$CO_2 \text{ remaining in test room at end of test} = (CO_{2 \text{ (test room end)}} - CO_{2 \text{ (test room start)}}) \cdot (\text{Scaling Factor}) \cdot (\text{Test Room Volume})$

$CO_2 \text{ generated by appliance} = (\text{Input Rate (Btu/h)} / 1000) \cdot (0.0167 \text{ SCFM} / 1000 \text{ Btu/h})$


$\text{Spillage} = \text{Total } CO_2 \text{ Leakage} / CO_2 \text{ generated by appliance}$

Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO ₂ (test room, base) (ppm):	414	414	414	414	414	414	414	414	414	414	414	414	414	414
CO ₂ (adjacent room, base) (ppm):	426	426	426	426	426	426	426	426	426	426	426	426	426	426
CO ₂ (test room) (ppm):	413	415	418	419	424	428	432	434	437	438	439	440	438	433
CO ₂ (adjacent room) (ppm):	431	434	433	434	434	434	436	436	437	437	439	439	439	438
Exhaust Fan Flow (ACFM):	259.0	259.0	259.0	259.0	259.0	259.0	259.0	259.0	259.0	259.0	259.0	259.0	259.0	259.0
Exhaust Fan Flow (SCFM):	247.6	247.6	247.6	247.6	247.6	247.6	247.6	247.6	247.6	247.6	247.6	247.6	247.6	247.6
Vent CO ₂ concentration (%) ¹ :	1.9	1.9	1.9	1.9	1.9	1.9	1.9	1.9	1.9	1.9	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	30.7	30.7	30.7	30.7	30.7	30.7	30.7	30.7	30.7	30.7	29.9	0.0	0.0	0.0
Scaling Factor:	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06
∴ CO ₂ (depressurization) Leakage (ft ³) =	-0.0009	-0.0009	-0.0003	-0.0003	0.0003	0.0009	0.0012	0.0015	0.0018	0.0018	0.0017	0.0017	0.0015	0.0009

¹ Vent CO₂ concentration measured at vent terminal (appliance operating at steady state conditions)

² Total combustion products exhausted from test room (including excess air & dilution air)

Test Room CO₂ at end of 7 minute test = 433 ppm
 Test Room CO₂ at start of test = 413 ppm
 Volume of test room = 1578 ft³
 CO₂ remaining in test room at end of test = 0.032 ft³
 Total CO₂ removed from test room over 7 minute test period = 0.0107 ft³
 Total CO₂ leakage = 0.0426 ft³
 CO₂ Generated by appliance during 5 minute burner ON time = 2.745 ft³
 Spillage (Total CO₂ leakage/ Appliance CO₂) = 1.6%



Transient Spillage Test at 50 Pa. Depressurization

Sample No.: 04-06-M278-4
Client: NRCan
Test Date: 5/3/2004

Appliance Exhausting into Test Room

CO_2 leakage per time base interval = $(CO_{2(\text{test room})} - CO_{2(\text{adjacent room})}) \cdot (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Products Flow}) \cdot (\text{Scaling Factor})$

CO_2 remaining in test room at end of test = $(CO_{2(\text{test room end})} - CO_{2(\text{test room start})}) \cdot (\text{Scaling Factor}) \cdot (\text{Test Room Volume})$

CO_2 generated by appliance = $(\text{Input Rate (Btu/h)/1000}) \cdot (0.0167 \text{ SCFM/1000 Btu/h})$


Spillage = $\text{Total } CO_2 \text{ Leakage} / CO_2 \text{ generated by appliance}$

Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO_2 (test room, base) (ppm) :	454	454	454	454	454	454	454	454	454	454	454	454	454	454
CO_2 (adjacent room, base) (ppm) :	441	441	441	441	441	441	441	441	441	441	441	441	441	441
CO_2 (test room) (ppm) :	440	542	660	776	892	982	1067	1178	1247	1348	1406	1380	1295	1235
CO_2 (adjacent room) (ppm) :	434	434	432	435	436	436	437	439	439	441	445	452	456	458
Exhaust Fan Flow (ACFM):	282.0	282.0	282.0	282.0	282.0	282.0	282.0	282.0	282.0	282.0	282.0	282.0	282.0	282.0
Exhaust Fan Flow (SCFM):	268.6	268.6	268.6	268.6	268.6	268.6	268.6	268.6	268.6	268.6	268.6	268.6	268.6	268.6
Vent CO_2 concentration (%):	1.9	1.9	1.9	1.9	1.9	1.9	1.9	1.9	1.9	1.9	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM)	30.7	30.7	30.7	30.7	30.7	30.7	30.7	30.7	30.7	30.7	29.9	0.0	0.0	0.0
Scaling Factor:	0.000001	0.000001	0.000001	0.000001	0.000001	0.000001	0.000001	0.000001	0.000001	0.000001	0.000001	0.000001	0.000001	0.000001
$\therefore CO_2$ (depressurization) Leakage (ft ³) =	-0.0010	0.0127	0.0289	0.0440	0.0595	0.0715	0.0829	0.0975	0.1067	0.1200	0.1273	0.1229	0.1109	0.1026

¹ Vent CO_2 concentration measured at vent terminal (appliance operating at steady state conditions)

² Total combustion products exhausted (including excess air & dilution air) - not used in calculation as appliance was venting into test room.

Test Room CO_2 at end of 7 minute test = 1235 ppm
 Test Room CO_2 at start of test = 440 ppm
 Volume of test room = 1578 ft³
 CO_2 remaining in test room at end of test = 1.255 ft³
 Total CO_2 removed from test room over 7 minute test period = 1.0866 ft³
 Total CO_2 leakage = 2.3412 ft³
 CO_2 Generated by appliance during 5 minute burner ON time = 2.74 ft³
 Spillage (Total CO_2 leakage/ Appliance CO_2) = 85.4%



Transient Spillage Test at 50 Pa. Depressurization

Sample No.: 04-06-M278-5
Client: NRCan
Test Date: 5/5/2004

$$CO_2 \text{ leakage per time base interval} = (CO_2 \text{ (test room)} - CO_2 \text{ (adjacent room)}) \cdot (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Products Flow}) \cdot (\text{Scaling Factor})$$

$$CO_2 \text{ remaining in test room at end of test} = (CO_2 \text{ (test room end)} - CO_2 \text{ (test room start)}) \cdot (\text{Scaling Factor}) \cdot (\text{Test Room Volume})$$

$$CO_2 \text{ generated by appliance} = (\text{Input Rate (Btu/h)/1000}) \cdot (0.0167 \text{ SCFM/1000 Btu/h})$$


$$\text{Spillage} = \text{Total } CO_2 \text{ Leakage} / CO_2 \text{ generated by appliance}$$

	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO ₂ (test room, base) (ppm):	446	446	446	446	446	446	446	446	446	446	446	446	446	446
CO ₂ (adjacent room, base) (ppm):	439	439	439	439	439	439	439	439	439	439	439	439	439	439
CO ₂ (test room) (ppm):	447	446	447	443	443	445	446	448	448	450	449	450	451	453
CO ₂ (adjacent room) (ppm):	440	440	440	439	440	440	440	442	444	446	448	449	451	452
Exhaust Fan Flow (ACFM):	286.4	286.4	286.4	286.4	286.4	286.4	286.4	286.4	286.4	286.4	286.4	286.4	286.4	286.4
Exhaust Fan Flow (SCFM):	279.4	279.4	279.4	279.4	279.4	279.4	279.4	279.4	279.4	279.4	279.4	279.4	279.4	279.4
Appliance CO ₂ concentration (%) ¹ :	7.6	7.6	7.6	7.6	7.6	7.6	7.6	7.6	7.6	7.6	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	20.4	20.4	20.4	20.4	20.4	20.4	20.4	20.4	20.4	20.4	19.0	0.0	0.0	0.0
Scaling Factor:	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06
∴ CO ₂ (depressurization) Leakage (ft ³) =	0.0000	0.0000	0.0001	-0.0005	-0.0006	-0.0003	-0.0002	-0.0002	-0.0006	-0.0005	-0.0010	-0.0009	-0.0009	-0.0008

¹ CO₂ concentration measured at appliance (during transient spillage test)

² Total combustion products exhausted (including excess air)

Test Room CO₂ at end of 7 minute test = 453 ppm
 Test Room CO₂ at start of test = 447 ppm
 Volume of test room = 1578 ft³
 CO₂ remaining in test room at end of test = 0.009 ft³
 Total CO₂ removed from test room over 7 minute test period = -0.0064 ft³
 Total CO₂ leakage = 0.0027 ft³
 CO₂ Generated by appliance during 5 minute burner ON time = 6.045 ft³
 Spillage (Total CO₂ leakage/ Appliance CO₂) = 0.04%



Transient Spillage Test at 50 Pa. Depressurization

Sample No.: 04-06-M278-6
Client: NRCan
Test Date: 12/5/2004

Test with 9" section of 2" ABS pipe on air intake. Pipe terminates with 90° elbow incorporating perforated disks (supplied)

$$CO_2 \text{ leakage per time base interval} = (CO_2 \text{ (test room)} - CO_2 \text{ (adjacent room)}) \cdot (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Products Flow}) \cdot (\text{Scaling Factor})$$

$$CO_2 \text{ remaining in test room at end of test} = (CO_2 \text{ (test room end)} - CO_2 \text{ (test room start)}) \cdot (\text{Scaling Factor}) \cdot (\text{Test Room Volume})$$

$$CO_2 \text{ generated by appliance} = (\text{Input Rate (Btu/h)/1000}) \cdot (0.0167 \text{ SCFM/1000 Btu/h})$$


$$\text{Spillage} = \text{Total } CO_2 \text{ Leakage} / CO_2 \text{ generated by appliance}$$

	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	Post Purge	6.00	6.50	7.00
Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO ₂ (test room, base) (ppm):	423	423	423	423	423	423	423	423	423	423	423	423	423	423
CO ₂ (adjacent room, base) (ppm):	436	436	436	436	436	436	436	436	436	436	436	436	436	436
CO ₂ (test room) (ppm):	426	427	426	427	427	427	428	430	427	428	429	431	425	426
CO ₂ (adjacent room) (ppm):	436	436	436	436	437	439	446	454	455	452	455	457	456	453
Exhaust Fan Flow (ACFM):	305.5	305.5	305.5	305.5	305.5	305.5	305.5	305.5	305.5	305.5	305.5	305.5	305.5	305.5
Exhaust Fan Flow (SCFM):	295.4	295.4	295.4	295.4	295.4	295.4	295.4	295.4	295.4	295.4	295.4	295.4	295.4	295.4
Appliance CO ₂ concentration (%) ¹ :	6.2	6.2	6.2	6.2	6.2	6.2	6.2	6.2	6.2	6.2	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	24.4	24.4	24.4	24.4	24.4	24.4	24.4	24.4	24.4	24.4	22.9	0.0	0.0	0.0
Scaling Factor:	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06
∴ CO ₂ (depressurization) Leakage (ft ³) =	0.0006	0.0006	0.0005	0.0006	0.0006	0.0006	0.0008	0.0011	0.0007	0.0008	0.0010	0.0013	0.0003	0.0004

¹ CO₂ concentration measured at appliance (during transient spillage test)

² Total combustion products exhausted (including excess air)

Test Room CO₂ at end of 7 minute test = 426 ppm
 Test Room CO₂ at start of test = 426 ppm
 Volume of test room = 1578 ft³
 CO₂ remaining in test room at end of test = -0.001 ft³
 Total CO₂ removed from test room over 7 minute test period = 0.0098 ft³
 Total CO₂ leakage = 0.0088 ft³
 CO₂ Generated by appliance during 5 minute burner ON time = 6.21 ft³
 Spillage (Total CO₂ leakage/ Appliance CO₂) = 0.14%



Transient Spillage Test at 50 Pa. Depressurization

Sample No.: 04-06-M278-7
Client: NRCan
Test Date: 7/6/2004

Note: Using Nova analyser to monitor test room, Beckman to monitor adjacent space
Standing pilot. Burner operated at max input. Fireplace blower set to max speed (on/off controlled by thermodisk)
 CO_2 leakage per time base interval = $(CO_2 (test\ room) - CO_2 (adjacent\ room)) \cdot (Exhaust\ Fan\ Flow + Appliance\ Exhaust\ Products\ Flow) \cdot (Scaling\ Factor)$
 CO_2 remaining in test room at end of test = $(CO_2 (test\ room\ end) - CO_2 (test\ room\ start)) \cdot (Scaling\ Factor) \cdot (Test\ Room\ Volume)$
 CO_2 generated by appliance = $(Input\ Rate\ (Btu/h)/1000) \cdot (0.0167\ SCFM/1000\ Btu/h)$
 Spillage = $Total\ CO_2\ Leakage / CO_2\ generated\ by\ appliance$


Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO ₂ (test room, base) (ppm) ² :	443	443	443	443	443	443	443	443	443	443	443	443	443	443
CO ₂ (adjacent room, base) (ppm) ² :	409	409	409	409	409	409	409	409	409	409	409	409	409	409
CO ₂ (test room) (ppm) ¹ :	443	444	450	468	483	501	508	519	530	539	544	550	557	548
CO ₂ (adjacent room) (ppm) ¹ :	416	385	420	413	394	426	414	400	429	416	411	435	412	411
Exhaust Fan Flow (ACFM):	278.3	278.3	278.3	278.3	278.3	278.3	278.3	278.3	278.3	278.3	278.3	278.3	278.3	278.3
Exhaust Fan Flow (SCFM):	273.7	273.7	273.7	273.7	273.7	273.7	273.7	273.7	273.7	273.7	273.7	273.7	273.7	273.7
Appliance CO ₂ concentration (%) ¹ :	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	0.0	0.0	0.0	0.0
Scaling Factor:	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06
∴ CO ₂ (depressurization) Leakage (ft ³) =	-0.0005	-0.0005	0.0003	0.0028	0.0049	0.0074	0.0083	0.0098	0.0114	0.0126	0.0132	0.0141	0.0150	0.0139

¹ CO₂ concentration measured at appliance (during transient spillage test)

² Total combustion products exhausted (including excess air) - not used in calculation as appliance is a direct vent unit.

Note: Oscillations of CO₂ (adjacent room) readings due to analyser operation. Average value of 413 ppm used for calculations.

Test Room CO₂ at end of 7 minute test = 548 ppm
 Test Room CO₂ at start of test = 443 ppm
 Volume of test room = 1578 ft³
 CO₂ remaining in test room at end of test = 0.166 ft³
 Total CO₂ removed from test room over 7 minute test period = 0.1128 ft³
 Total CO₂ leakage = 0.2789 ft³
 CO₂ Generated by appliance during 5 minute burner ON time = 2.1 ft³
 Spillage (Total CO₂ leakage/ Appliance CO₂) = 13.3%



Transient Spillage Test at 50 Pa. Depressurization


Sample No.: 04-06-M278-7
Client: NRCan
Test Date: 8/6/2004

Note: Using Nova analyser to monitor test room, Beckman to monitor adjacent space
Standing pilot. Burner operated at max input. Fireplace blower set to max speed (on/off controlled by thermodisk)
Additional circulating fan installed in test room to improve mixing and ensure uniform environment
 CO_2 leakage per time base interval = $(CO_2 \text{ (test room)} - CO_2 \text{ (adjacent room)}) \cdot (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Products Flow}) \cdot (\text{Scaling Factor})$
 CO_2 remaining in test room at end of test = $(CO_2 \text{ (test room end)} - CO_2 \text{ (test room start)}) \cdot (\text{Scaling Factor}) \cdot (\text{Test Room Volume})$
 CO_2 generated by appliance = $(\text{Input Rate (Btu/h)} / 1000) \cdot (0.0167 \text{ SCFM} / 1000 \text{ Btu/h})$
Spillage = Total CO_2 Leakage / CO_2 generated by appliance

Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO_2 (test room, base) (ppm):	450	450	450	450	450	450	450	450	450	450	450	450	450	450
CO_2 (adjacent room, base) (ppm):	411	411	411	411	411	411	411	411	411	411	411	411	411	411
CO_2 (test room) (ppm):	456	485	501	514	520	528	538	547	550	558	562	547	540	531
CO_2 (adjacent room) (ppm):	404	399	424	401	403	424	397	408	424	393	412	424	391	417
Exhaust Fan Flow (ACFM):	272.0	272.0	272.0	272.0	272.0	272.0	272.0	272.0	272.0	272.0	272.0	272.0	272.0	272.0
Exhaust Fan Flow (SCFM):	266.2	266.2	266.2	266.2	266.2	266.2	266.2	266.2	266.2	266.2	266.2	266.2	266.2	266.2
Appliance CO_2 concentration (%) ¹ :	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	0.0	0.0	0.0	0.0
Scaling Factor:	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06
$\therefore CO_2$ (depressurization) Leakage (ft ³) =	0.0011	0.0049	0.0071	0.0088	0.0096	0.0106	0.0120	0.0131	0.0136	0.0146	0.0151	0.0132	0.0121	0.0110

¹ CO_2 concentration measured at appliance (during transient spillage test)
² Total combustion products exhausted (including excess air) - not used in calculation as appliance is a direct vent unit.
Note: Oscillations of CO_2 (adjacent room) readings due to analyser operation. Average value of 409 ppm used for calculations.

Test Room CO_2 at end of 7 minute test = 531 ppm
Test Room CO_2 at start of test = 456 ppm
Volume of test room = 1578 ft³
 CO_2 remaining in test room at end of test = 0.118 ft³
Total CO_2 removed from test room over 7 minute test period = 0.1467 ft³
Total CO_2 leakage = 0.2647 ft³
 CO_2 Generated by appliance during 5 minute burner ON time = 2.07 ft³
Spillage (Total CO_2 leakage/ Appliance CO_2) = 12.8%



Transient Spillage Test at 20 Pa. Depressurization

Sample No.: 04-06-M278-7
Client: NRCan
Test Date: 8/6/2004

Note: Using Nova analyser to monitor test room, Beckman to monitor adjacent space
Standing pilot. Burner operated at max input. Fireplace blower set to max speed (on/off controlled by thermodisk)
Additional circulating fan installed in test room to improve mixing and ensure uniform environment
 CO_2 leakage per time base interval = $(CO_2 \text{ (test room)} - CO_2 \text{ (adjacent room)}) \cdot (\text{Exhaust Fan Flow} + \text{Appliance Exhaust Products Flow}) \cdot (\text{Scaling Factor})$
 CO_2 remaining in test room at end of test = $(CO_2 \text{ (test room end)} - CO_2 \text{ (test room start)}) \cdot (\text{Scaling Factor}) \cdot (\text{Test Room Volume})$
 CO_2 generated by appliance = $(\text{Input Rate (Btu/h)} / 1000) \cdot (0.0167 \text{ SCFM} / 1000 \text{ Btu/h})$
Spillage = Total CO_2 Leakage / CO_2 generated by appliance


Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO_2 (test room, base) (ppm) ¹ :	455	455	455	455	455	455	455	455	455	455	455	455	455	455
CO_2 (adjacent room, base) (ppm) ¹ :	421	421	421	421	421	421	421	421	421	421	421	421	421	421
CO_2 (test room) (ppm) ² :	455	467	472	475	478	479	484	484	489	489	492	485	485	482
CO_2 (adjacent room) (ppm) ² :	405	413	430	401	417	432	398	421	430	396	424	429	394	426
Exhaust Fan Flow (ACFM):	142.4	142.4	142.4	142.4	142.4	142.4	142.4	142.4	142.4	142.4	142.4	142.4	142.4	142.4
Exhaust Fan Flow (SCFM):	139.0	139.0	139.0	139.0	139.0	139.0	139.0	139.0	139.0	139.0	139.0	139.0	139.0	139.0
Appliance CO_2 concentration (%) ¹ :	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	0.0	0.0	0.0	0.0
Scaling Factor:	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06
$\therefore CO_2$ (depressurization) Leakage (ft ³) =	0.0004	0.0013	0.0016	0.0018	0.0020	0.0021	0.0024	0.0024	0.0028	0.0028	0.0030	0.0025	0.0025	0.0023

¹ CO_2 concentration measured at appliance (during transient spillage test)

² Total combustion products exhausted (including excess air) - not used in calculation as appliance is a direct vent unit.

Note: Oscillations of CO_2 (adjacent room) readings due to analyser operation. Average value of 415 ppm used for calculations.

Test Room CO_2 at end of 7 minute test = 482 ppm
Test Room CO_2 at start of test = 455 ppm
Volume of test room = 1578 ft³
 CO_2 remaining in test room at end of test = 0.044 ft³
Total CO_2 removed from test room over 7 minute test period = 0.0299 ft³
Total CO_2 leakage = 0.0736 ft³
 CO_2 Generated by appliance during 5 minute burner ON time = 2.09 ft³
Spillage (Total CO_2 leakage/ Appliance CO_2) = 3.5%



Transient Spillage Test at 5 Pa. Depressurization


Sample No.: 04-06-M278-7
Client: NRCan
Test Date: 8/6/2004

Note: Using Nova analyser to monitor test room, Beckman to monitor adjacent space
Standing pilot. Burner operated at max input. Fireplace blower set to max speed (on/off controlled by thermodisk)
Additional circulating fan installed in test room to improve mixing and ensure uniform environment
 CO_2 leakage per time base interval = $(CO_2 (test\ room) - CO_2 (adjacent\ room)) \cdot (Exhaust\ Fan\ Flow + Appliance\ Exhaust\ Products\ Flow) \cdot (Scaling\ Factor)$
 CO_2 remaining in test room at end of test = $(CO_2 (test\ room\ end) - CO_2 (test\ room\ start)) \cdot (Scaling\ Factor) \cdot (Test\ Room\ Volume)$
 CO_2 generated by appliance = $(Input\ Rate\ (Btu/h)/1000) \cdot (0.0167\ SCFM/1000\ Btu/h)$
Spillage = Total CO_2 Leakage / CO_2 generated by appliance

Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO_2 (test room, base) (ppm):	441	441	441	441	441	441	441	441	441	441	441	441	441	441
CO_2 (adjacent room, base) (ppm):	412	412	412	412	412	412	412	412	412	412	412	412	412	412
CO_2 (test room) (ppm):	441	441	441	441	441	441	441	441	441	441	441	441	442	442
CO_2 (adjacent room) (ppm):	424	392	430	419	398	429	414	399	431	412	403	430	409	406
Exhaust Fan Flow (ACFM):	55.9	55.9	55.9	55.9	55.9	55.9	55.9	55.9	55.9	55.9	55.9	55.9	55.9	55.9
Exhaust Fan Flow (SCFM):	54.5	54.5	54.5	54.5	54.5	54.5	54.5	54.5	54.5	54.5	54.5	54.5	54.5	54.5
Appliance CO_2 concentration (%) ¹ :	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	5.1	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	8.7	0.0	0.0	0.0	0.0
Scaling Factor:	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06
$\therefore CO_2$ (depressurization) Leakage (ft ³) =	0.0000	-0.0001	-0.0001	-0.0001	-0.0001	-0.0001	-0.0001	-0.0001	-0.0001	-0.0001	-0.0001	0.0000	0.0000	0.0000

¹ CO_2 concentration measured at appliance (during transient spillage test)
² Total combustion products exhausted (including excess air) - not used in calculation as appliance is a direct vent unit.
Note: Oscillations of CO_2 (adjacent room) readings due to analyser operation. Average value of 414 ppm used for calculations.

Test Room CO_2 at end of 7 minute test = 442 ppm
Test Room CO_2 at start of test = 441 ppm
Volume of test room = 1578 ft³
 CO_2 remaining in test room at end of test = 0.001 ft³
Total CO_2 removed from test room over 7 minute test period = -0.0007 ft³
Total CO_2 leakage = 0.0001 ft³
 CO_2 Generated by appliance during 5 minute burner ON time = 2.08 ft³
Spillage (Total CO_2 leakage/ Appliance CO_2) = 0.01%



Transient Spillage Test at 50 Pa. Depressurization

Sample No.: 04-06-M278-8
Client: NRCan
Test Date: 9/6/2004

Note: Using Beckman analyser to monitor test room, Nova to monitor adjacent space
Standing pilot. Burner operated at max input. No integral blower on this unit.

Additional circulating fan installed in test room to improve mixing and ensure uniform environment

CO_2 leakage per time base interval = $(CO_2 (test\ room) - CO_2 (adjacent\ room)) \cdot (Exhaust\ Fan\ Flow + Appliance\ Exhaust\ Products\ Flow) \cdot (Scaling\ Factor)$

CO_2 remaining in test room at end of test = $(CO_2 (test\ room\ end) - CO_2 (test\ room\ start)) \cdot (Scaling\ Factor) \cdot (Test\ Room\ Volume)$

CO_2 generated by appliance = $(Input\ Rate\ (Btu/h)/1000) \cdot (0.0167\ SCFM/1000\ Btu/h)$

Spillage = Total CO_2 Leakage / CO_2 generated by appliance

Time (minutes):	0.50	1.00	1.50	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	6.50	7.00
CO_2 (test room, base) (ppm):	414	414	414	414	414	414	414	414	414	414	414	414	414	414
CO_2 (adjacent room, base) (ppm):	409	409	409	409	409	409	409	409	409	409	409	409	409	409
CO_2 (test room) (ppm):	412	413	413	414	415	415	416	416	416	416	417	416	416	415
CO_2 (adjacent room) (ppm):	406	404	405	409	405	406	410	407	403	406	404	405	404	407
Exhaust Fan Flow (ACFM):	291.4	291.4	291.4	291.4	291.4	291.4	291.4	291.4	291.4	291.4	291.4	291.4	291.4	291.4
Exhaust Fan Flow (SCFM):	281.7	281.7	281.7	281.7	281.7	281.7	281.7	281.7	281.7	281.7	281.7	281.7	281.7	281.7
Appliance CO_2 concentration (%) ¹ :	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	0.0	0.0	0.0	0.0
Combustion Products Flow (SCFM) ² :	15	15	15	15	15	15	15	15	15	15	0	0	0	0
Scaling Factor:	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06	1.00E-06
$\therefore CO_2$ (depressurization) Leakage (ft ³) =	0.0002	0.0006	0.0005	0.0001	0.0007	0.0007	0.0001	0.0005	0.0011	0.0008	0.0011	0.0009	0.0009	0.0005

¹ Vent CO_2 concentration measured at appliance (during transient spillage test)

² Total combustion products exhausted (including excess air) - not used in calculation as appliance is a direct vent unit.

Test Room CO_2 at end of 7 minute test = 415 ppm
 Test Room CO_2 at start of test = 412 ppm
 Volume of test room = 1578 ft³
 CO_2 remaining in test room at end of test = 0.0048 ft³
 Total CO_2 removed from test room over 7 minute test period = 0.0086 ft³
 Total CO_2 leakage = 0.0134 ft³
 CO_2 Generated by appliance during 5 minute burner ON time = 1.95 ft³
 Spillage (Total CO_2 leakage/ Appliance CO_2) = 0.7%

